



Test Report: LPF-16D-15

16W Single Output Switching Power Supply

■ DESIGN VERIFY TEST

Output Function Test

Input Function Test

Protection Function Test

Component Stress Test

■ SAFETY & E.M.C. TEST

Safety Test

E.M.C. Test

■ RELIABILITY TEST

ENVIRONMENT TEST

■ DESIGN VERIFY TEST

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1 : 150 mVp-p (Max)	I/P : 230VAC O/P : FULL LOAD Ta : 25°C	V1 : 22 mVp-p (Max)	P
2	CONSTANT CURRENT REGION	V1= 7.5V~15V	I/P : 230VAC O/P : CV MODE Ta : 25°C	O/P= 7.5V : 1.094 A O/P= 14V : 1.092 A	P
3	OUTPUT VOLTAGE TOLERANCE	V1 : 4 %~ -4 % (Max)	I/P : 100 VAC / 305 VAC O/P : FULL/ MIN LOAD Ta : 25°C	V1 : 0.807 %~ -0.213 %	P
4	LINE REGULATION	V1 : 0.5 %~ -0.5 % (Max)	I/P : 100 VAC ~ 305 VAC O/P : FULL LOAD Ta : 25°C	V1 : 0.007 %~ -0.007 %	P
5	LOAD REGULATION	V1 : 1.5 %~ -1.5 % (Max)	I/P : 230 VAC O/P : FULL ~MIN LOAD Ta : 25°C	V1 : 0.100 %~ -0.113 %	P
6	SET UP TIME	230VAC : 500 ms (Max) 115VAC : 1500 ms(Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 337.722 ms 115VAC/ 385.473 ms	P
7	RISE TIME	230VAC : 80 ms (Max) 115VAC : 80 ms (Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 8 ms 115VAC/ 8 ms	P
8	HOLD UP TIME	230VAC : 16 ms (TYP) 115VAC : 16 ms (TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 120 ms 115VAC/ 121 ms	P
9	OVER/UNDERSHOOT TEST	< ±5%	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	TEST : <5 %	P
10	DYNAMIC LOAD	V1 : 1500 mVp-p	I/P : 230 VAC (1).O/P : FULL /Min LOAD 90%DUTY/ 1KHZ (2).O/P : FULL /Min LOAD 50%DUTY/ 120HZ Ta : 25°C	(1) 181 mVp-p (2) 291 mVp-p	P

11	DIMMER TEST	SPEC:										
		*Output constant current level can be adjusted through output cable by 1 ~ 10Vdc, PWM signal or resistor between ADJ1(+) and ADJ2(-).										
		*Reference resistance value for output current adjustment (Typical)										
		Resistance value	10K	20K	30K	40K	50K	60K	70K	80K	90K	100K
		Output current	10%	20%	30%	40%	50%	60%	70%	80%	90%	100%
		*1 ~ 10V dimming function for output current adjustment (Typical)										
		Dimming value	1V	2V	3V	4V	5V	6V	7V	8V	9V	10V
		Output current	10%	20%	30%	40%	50%	60%	70%	80%	90%	100%
		*10V PWM signal for output current adjustment (Typical)										
		Duty value	10%	20%	30%	40%	50%	60%	70%	80%	90%	100%
		Output current	10%	20%	30%	40%	50%	60%	70%	80%	90%	100%
TEST RESULT: I/P : 230 VAC ; Ta : 25°C												
1	Resistance value	10K	20K	30K	40K	50K	60K	70K	80K	90K	100K	
	Output current	0.083A	0.193A	0.298A	0.413A	0.525A	0.634A	0.741A	0.857A	0.966A	1.061A	
	%	7.76%	18.04%	27.85%	38.60%	49.07%	59.25%	69.25%	80.09%	90.28%	99.16%	
2	Dimming value	1V	2V	3V	4V	5V	6V	7V	8V	9V	10V	
	Output current	0.085A	0.195A	0.304A	0.417A	0.528A	0.638A	0.747A	0.860A	0.970A	1.068A	
	%	7.94%	18.22%	28.41%	38.97%	49.35%	59.63%	69.81%	80.37%	90.65%	99.81%	
3	Duty value	10%	20%	30%	40%	50%	60%	70%	80%	90%	100%	
	Output current	0.086A	0.197A	0.308A	0.419A	0.531A	0.642A	0.752A	0.864A	0.974A	1.073A	
	%	8.04%	18.41%	28.79%	39.16%	49.63%	60.00%	70.28%	80.75%	91.03%	100.3%	

P

INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	100VAC~305 VAC	I/P : TESTING O/P : FULL LOAD Ta : 25°C I/P : LOW-LINE-3V=97 V HIGH-LINE=305 V O/P : FULL/MIN LOAD ON : 30 Sec . OFF : 30 Sec 10MIN (AC POWER ON/OFF NO DAMAGE)	85 V~305V TEST : OK	P
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P : 100 VAC ~ 305 VAC O/P : FULL-MIN LOAD Ta : 25°C	TEST : OK	P
3	POWER FACTOR	0.95 / 230 VAC(TYP) 0.97 / 115 VAC(TYP) 0.92 / 277 VAC(TYP)	I/P : 230 VAC I/P : 115 VAC I/P : 277 VAC O/P : FULL LOAD Ta : 25°C	PF= 0.973 / 100% PF= 0.995 / 100% PF= 0.938 / 100%	P
4	EFFICIENCY	83% (TYP)	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	83.54 %	P
5	INPUT CURRENT	230V/ 0.25 A (TYP) 115V/ 0.4 A (TYP) 277V/ 0.2 A (TYP)	I/P : 230 VAC I/P : 115 VAC I/P : 277 VAC O/P : FULL LOAD Ta : 25°C	I = 0.083 A/ 230 VAC I = 0.164 A/ 115 VAC I = 0.071 A/ 277 VAC	P
6	INRUSH CURRENT	230V/ 50 A (TYP) COLD START	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	I = 36.0 A/ 230 VAC	P
7	LEAKAGE CURRENT	< 0.75 mA / 240 VAC	I/P : 240 VAC O/P : Min LOAD Ta : 25°C	L-CASE : 0.003 mA N-CASE : 0.003 mA	P

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	95 % ~ 108 %	I/P : 230 VAC I/P : 115 VAC O/P : TESTING Ta : 25°C	102.26 %/ 230 VAC 102.25 %/ 115 VAC Constant Current Limiting ,recovers automatically after fault condition is removed.	P
2	OVER VOLTAGE PROTECTION	CH1 : 17.5 V ~ 21 V	I/P : 230 VAC I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	19.1 V/ 230 VAC 19.1 V/ 115 VAC Shut down and latch off o/p voltage, re-power on to recover	P
3	OVER TEMPERATURE PROTECTION	SPEC : TSW1 : 100±5°C O.T.P. NO DAMAGE	I/P : 230 VAC O/P : FULL LOAD	O.T.P. Active Shut down o/p voltage , recovers automatically after temperature goes down	P
4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P : 305 VAC O/P : FULL LOAD Ta : 25°C	NO DAMAGE Hiccup mode, recovers automatically after fault condition is removed.	P

COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor (D to S) or (C to E) Peak Voltage	U2 Rated : IP7518: 700V / 2A	I/P : High-Line +3V = 308 V O/P : (1)Full Load Turn on (2) Output Short (3)Full load continue Ta : 25°C	(1) 640 V (2) 486 V (3) 632 V	P
2	Diode Peak Voltage	D101 Rated : YG868C08: 80V / 30A	I/P : High-Line +3V = 308 V O/P : (1)Full Load Turn on (2)Output Short (3)Full load continue Ta : 25°C	(1) 64.0 V (2) 40.6 V (3) 63.6 V	P
3	Input Capacitor Voltage	C5 Rated : 22u/450V 105°C 16*20 RH	I/P : High-Line +3V = 308 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 436 V (2) 440 V (3) 428 V	P
4	Control IC Voltage Test	U 2 Rated : IP7518:30V	I/P : High-Line +3V = 308 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 21.2 V (2) 13.9 V (3) 19.5 V	P
5	Power Transistor (D to S) or (C to E) Peak Voltage	Q1 Rated : NDF10N60ZG: 600V/ 10 A	I/P : High-Line +3V = 308 V O/P : (1)Full Load Turn on (2) Output Short (3)Full load continue Ta : 25°C	(1) 494 V (2) 424 V (3) 440 V	P

■ SAFETY & E.M.C. TEST

SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P : 3.75 KVAC/min	I/P-O/P : 4 KVAC/min Ta : 25°C	I/P-O/P : 1.459 mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P : 500VDC>100MΩ	I/P-O/P : 500 VDC Ta : 25°C/70% RH	I/P-O/P : >9999 MΩ NO DAMAGE	P
3	APPROVAL	TUV : Certificate NO : UL : File NO :			N/A

E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2 CLASS C	I/P:230VAC/240VAC/220VAC50HZ O/P:100%,75%,50%LOAD CLASS C ≥ 50% Ta:25°C	PASS	P
2	CONDUCTION	EN55015	I/P: 230 VAC (50HZ)/115V[60HZ] O/P:FULL/50% LOAD Ta:25°C	PASS Test by certified Lab	P
3	RADIATION	EN55015	I/P: 230 VAC (50HZ)/115V[60HZ] O/P:FULL LOAD Ta:25°C	PASS Test by certified Lab	P
4	E.S.D	EN61000-4-2 LIGHT INDUSTRY AIR:8KV / Contact:4KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
5	E.F.T	EN61000-4-4 LIGHT INDUSTRY INPUT: 1KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
6	SURGE	IEC61000-4-5 INDUSTRY L-N :2KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
7	Test by certified Lab & Test Report Prepare				

■ RELIABILITY TEST

ENVIRONMENT TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	TEMPERATURE RISE TEST	MODEL : LPF-16D-12 1. ROOM AMBIENT BURN-IN : 2.5 HRS I/P : 230VAC O/P : 95% LOAD Ta=32.2 °C 2. HIGH AMBIENT BURN-IN : 3.5 HRS I/P : 230VAC O/P : 95% LOAD Ta=50.1 °C			P
2	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P : 305VAC/100VAC O/P : 95 % LOAD Ta= -40°C	TEST : OK	P
3	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 50 °C NO DAMAGE	I/P : 305 VAC O/P : 95% LOAD Ta= 50 °C HUMIDITY= 95 %R.H	TEST : OK	P
4	TEMPERATURE COEFFICIENT	± 0.03 %(0~50°C)	I/P : 230 VAC O/P : 95% LOAD	± 0.002 %(0~50°C)	P
5	STORAGE TEMPERATURE TEST	1. Thermal shock Temperature : -45°C~ +85°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 5 CYCLE 5. Input/Output condition : STATIC		OK	P
6	THERMAL SHOCK TEST	1. Thermal shock Temperature : -45°C~ +55°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 10 CYCLE 5. Input/Output condition : 230VAC/Full Load AC ON/OFF TEST turn on 58sec ; turn off 2sec		OK	P
7	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10~500Hz (3) Sweep Time : 12min/sweep cycle (4) Acceleration : 2G (5) Test Time : 72min in each axis (X.Y.Z) (6) Ta : 25°C		TEST : OK	P



16W Single Output Switching Power Supply

LPF-16D series

8	CAPACITOR LIFE CYCLE	LPF-16-12:SUPPOSE C105 IS THE MOST CRITICAL COMPONENT (1) I/P : 230VAC O/P : FULL LOAD Ta=25 °C LIFE TIME (2) I/P : 230VAC O/P : FULL LOAD Ta=50 °C LIFE TIME (3) I/P : 230VAC O/P : 75% LOAD Ta=50 °C LIFE TIME	(1) 452611.8 HRS (2) 91294.2 HRS (3) 119635.2 HRS	P
9	MTBF	Conducted by Parts Stress Analysis Prediction 3572.8K hrs min. Telcordia SR-332 (Bellcore); 391.6K hrs min. MIL-HDBK-217F (25°C)		P
10	DMTBF/Accelerated Life Test	Demonstration Mean Time Between Failure(Expected Life) : 50,000 hours @ Tcase70°C		P

SAMPLE	TEST RESULT	TESTER	APPROVAL
PRODUCT SAMPLE	PASS	ZOULF	HOWAY

2009/08/04 A50-F023