



Test Report : RSDW20F-03

20W 2"x1" Package Reliable Railway DC-DC Converter

■ DESIGN VERIFY TEST

Output Function Test

Input Function Test

Protection Function Test

■ SAFETY TEST

Safety Test

■ RELIABILITY TEST

Environment Test

Other Test

DESIGN VERIFY TEST

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDITC
1	VOLTAGE ACCURACY	-1.5% ~ +1.5 %	I/P:24VDC O/P:FULL LOAD Ta:25°C	-0.08%	P
2	RIPPLE & NOISE	60 mVp-p	I/P:24VDC O/P:FULL LOAD Ta:25°C	12 mV	P
3	LINE REGULATION	-0.2% ~ +0.2%	I/P:9VDC~36VDC O/P:FULL LOAD Ta:25°C	-0.02% ~ +0.00%	P
4	LOAD REGULATION	-0.5% ~ +0.5%	I/P:24VDC O/P:10% LOAD~FULL LOAD Ta:25°C	-0.11% ~ +0.12%	P

INPUT FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDITC
1	EFFICIENCY	87%	I/P:24VDC O/P:FULL LOAD Ta:25°C	87.05%	P
2	DC CURRENT	869 mA / FULL LOAD 55 mA / NO LOAD	I/P:24VDC O/P:NO / FULL LOAD Ta:25°C	868.0 mA / FULL LOAD 34.6 mA / NO LOAD	P
3	UNDER VOLTAGE LOCKOUT	POWER UP 8.8VDC (Typ) POWER DOWN 8VDC (Typ)	I/P:TESTING O/P:FULL LOAD Ta:25°C	POWER UP 8.7VDC POWER DOWN 8.0VDC	P

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDITC
1	SHORT PROTECTION	CONTINUOUS	I/P:36VDC O/P:FULL LOAD Ta:25°C	AUTOMATIC RECOVERY	P
2	OVER LOAD PROTECTION	110~160%	I/P:24VDC O/P:TESTING Ta:25°C	120.2%	P

CONTROL FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	REMOTE CONTROL	Power on : >5.5~75Vdc or open circuit Power off : R.C <1.2Vdc or short	I/P:24VDC O/P:FULL LOAD Ta:25°C	Power on : R.C>2.7Vdc or Open Power off : R.C<2.3Vdc or Short	P
2	TRIM	-10%~ +10% (Typ) Trim ~ +Vout Trim DOWN Trim ~ -Vout Trim UP Using 500K ohms VR	I/P:24VDC O/P:FULL LOAD Ta:25°C	Trim DOWN -13.27% Trim UP +12.85%	P

■ SAFETY TEST

SAFETY TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDITC
1	WITHSTAND VOLTAGE	I/P-O/P:1.5K VDC/min	I/P-O/P:1.5K VDC/min Ta:25°C	I/P-O/P: 0.002mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P:500VDC>100MΩ	I/P-O/P:500 VDC Ta:25°C	I/P-O/P>100MΩ NO DAMAGE	P

■ RELIABILITY TEST

ENVIRONMENT TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDITC										
1	TEMPERATURE RISE TEST	1. ROOM AMBIENT BURN-IN : 4HRS I/P:24VDC O/P:FULL LOAD Ta=25°C 2. HIGH AMBIENT BURN-IN : 4HRS I/P:24VDC O/P:FULL LOAD Ta=73°C			P										
		<table border="1"> <thead> <tr> <th>NO</th> <th>Position</th> <th>P/N</th> <th>1</th> <th>2</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>CASE</td> <td>CENTER</td> <td>58.2°C</td> <td>101.6°C</td> </tr> </tbody> </table>				NO	Position	P/N	1	2	1	CASE	CENTER	58.2°C	101.6°C
NO	Position	P/N	1	2											
1	CASE	CENTER	58.2°C	101.6°C											
2	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 4 HOURS	I/P:24VDC O/P: FULL LOAD Ta= -40°C	TEST : OK	P										

OTHER

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDITC
1	MTBF	MIL-HDBK-217F,GB,25°C TOTAL FAILURE RATE : 1.38888 M.T.B.F : 720K HRS			P

TEST RESULT	TESTER	APPROVAL
PASS	ARCHEN HSIAO	PETER CHENG